

PASS_M0X-L3-M00_72.5kV_100kV & M0_145kV_170kV & M0S_245kV -Training Agenda

PASS PSC- Technical Training

PREPARED BY	STATUS	SECURITY LEVEL		
Davide Rossato	Approved	Internal		
APPROVED BY	APPROVAL DATE			
Diego Gaggero	2023-01-18			
OWNER	DOCUMENT KIND			
Davide Rossato	Agenda			
TITLE				
PASS_M0X-L3-M00_72.5kV_100kV & M0_145kV_170kV & M0S_245kV -Training Agenda				
OWNING ORGANIZATION	DOCUMENT ID	REV.	LANG.	PAGE
IT-Lodi-2657-Field Service	2GHE006793	B	en	1/5
Hitachi Energy		© 2022 Hitachi Energy. All rights reserved		

© 2022 Hitachi Energy. All rights reserved.

Course goal:

This training's primary objective is to ensure a safe and effective operating process that focuses primarily upon the Installation and commissioning (I&C) aspects of Hybrid PASS (Plug and Switch System).

Main learning objectives:

- Understanding of Detailed component assembly
- How to carryout Minor repairs
- Theoretical and practical knowledge of circuit-breaker's Relevant drive control
- Thorough understanding of the functioning mechanism for the relevant disconnector's Drive.
- comprehensive understanding of handling SF₆ gas.
- Foundational knowledge about Maintenance inspection aspects
- Understanding of how to conduct on-site testing, maintaining H&S aspects, and reporting to the PSC (Product Service center).
- Practical Part of Functionality, Setting and Troubleshooting of Circuit breaker and disconnector drive mechanism.
- Functionality & 3 step for setting Disconnectors and relevant drive mechanism Theoretical Part
- Functionality & 3 step for setting Disconnectors and relevant drive mechanism Practical Part
- SF₆ Handling
- Maintenance concept
- Installation of the module On-site activity: Theoretical Part
- Commissioning of the module On-site activity: Theoretical Part
- Installation and Commissioning PASS Installation (simulated) – Practical Part
- Installation and Commissioning: SF₆ Gas Filling and LCC Power supply and Pre-Commissioning checks – Practical Part
- Commissioning & Reporting – Practical Part

Prerequisites:

- Training in electrical and mechanical subjects
- Professional experience
- A certification that allows to perform an activity where it is necessary to work on electrical system, both dead and live working at LV or to work in the vicinity of HV systems.
- SF₆ certification (relevant in EU)
- Sufficient English language skills
- PPE (Personal Protective Equipment)
- HSE (Health Safety and Environment) and PICW (Person in charge of work) training done
- Heavy loads training
- First aid/emergency

Topics:

- Training and Certification Process
- Hybrid PASS Portfolio
- PASS Overall Assembly
- Theoretical Part of Functionality, Setting and Troubleshooting of Circuit breaker and disconnector drive mechanism.

This is a theoretical and practical training.

Certification:

This is a certification course. A certificate will be issued after the successful completion of the On-site I&C activity which will be conducted by the Training Center.

Duration:

Two Weeks

Enrolments:

- FSE's can fill the details in the form given in the below link for enrolment

https://forms.office.com/Pages/ResponsePage.aspx?id=2eYxe-Gzc0Uyexh3CtBMxlepgS_A8TdVFjOFVnAownc-tUMFJHWEpJSEJOODVOTExCVjhDM1dWRkNQNS4u

And send your request to

it-training-psc_lodi@hitachienergy.com

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE006793	B	en	2/5

© 2022 Hitachi Energy. All rights reserved.

Day	Subject	Location
1	Training and Certification process presentation	Lodi Factory
	<ul style="list-style-type: none"> • Introduction to Basic Trainings • Certification Concept • Different levels of Certification • Certification Process 	
	Hybrid PASS Portfolio presentation	
	<ul style="list-style-type: none"> • Introduction to Hybrid high voltage switchgear • Product Description • PASS Types and Families • Additional Features • Commitment 	
2	Hybrid PASS Major components	Lodi Factory
	<ul style="list-style-type: none"> • Bushings • Current Transformer • Voltage Transformer • Circuit Breakers • Disconnecter 	
	Factory Visit	
	Circuit Breaker and relevant drive mechanism	
	<ul style="list-style-type: none"> • Introduction • Technical Description of the equipment • Functionality of the equipment • Setting and Troubleshooting of the equipment- Theoretical Part • Setting and Troubleshooting of the equipment- Practical Part 	
3	Disconnectors and relevant drive mechanism	Lodi Factory
	<ul style="list-style-type: none"> • Introduction • Technical Description of the equipment • Functionality of the equipment • Functionality & 3 step for setting the equipment – Theoretical Part • Functionality & 3 step for setting the equipment –Practical Part 	

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE006793	B	en	3/5

Day	Subject	Location
4	Disconnectors and relevant drive mechanism	Lodi Factory
	<ul style="list-style-type: none"> • Functionality & 3 step for setting the equipment – Practical Part • Operating Mechanism • Setting of different placements of the Disconnector Drive Mechanism 	
5	SF₆ Handling	Lodi Factory
	<ul style="list-style-type: none"> • Characteristics of SF₆ • SF₆ Health & Safety aspects • General Safety rules • Handling SF₆ During Installation and Commissioning • Rupture Disc – Theoretical & Practical part • Gas Compartment treatment – Theoretical & Practical part 	
6	Maintenance Concept	Lodi Factory
	<ul style="list-style-type: none"> • Concept clarification • Maintenance Inspections • Maintenance Plan • Overhaul - Theoretical Part • Certification requirement 	
7	Installation of the module: On-site (Theoretical Part)	Lodi Factory
	<ul style="list-style-type: none"> • General Information • Specifying the Technical referral documents • Service Document requirement for I&C Activity • On-site Installation: Introduction • Fixing of Vertical Support • Installation of the main shipping unit • Lateral poles rotation • Earth cables connection 	
7	Installation and Commission: On-site (Practical Part)	Lodi Factory
	<ul style="list-style-type: none"> • PASS Installation (simulated) – Practical Part • Lateral poles rotation • Linking Shaft Installation of Circuit Breaker and Disconnector • Earth cables connection • SF₆ Gas Filling – Practical Part • LCC (Local control cubicle) Power supply • Pre-Commissioning checks 	

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE006793	B	en	4/5

© 2022 Hitachi Energy. All rights reserved.

Day	Subject	Location
8	Installation and Commission: On-site (Practical Part)	Lodi Factory
	<ul style="list-style-type: none"> • Commissioning requirements • Checklist for commissioning • Documentation • Findings reporting (For internal use) • Site Test Report (For Customers) • Actions taken to rectify any deficiencies 	
9	Factory On-site Assessment for Participants	Lodi Factory
	<ul style="list-style-type: none"> • Installation and Commissioning • Light Troubleshooting • Review of I&C action & reporting 	
10	Factory On-Site Assessment Evaluation	Lodi Factory
	<ul style="list-style-type: none"> • Evaluation done by the Technical Trainer 	
10	Conclusion	Lodi Factory
	<ul style="list-style-type: none"> • Sharing the full-filled supervision Report • Sharing confirmation of attendance along with the current status of Authorization to perform on-site activity (Supervised by Level 3/Above Assessor) 	

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE006793	B	en	5/5