

GIS-L3-ELK14_300&ELK3_420-Training Agenda Level 3 Field Service Engineer Training

TRAINING CENTER SWITZERLAND - COURSE DESCRIPTION

PREPARED BY	STATUS	SECURITY LEVEL			
Jenisija Karunakaran	Approved	Internal	Internal		
APPROVED BY	APPROVAL DATE				
Zsofia Fodor	2022-12-07				
OWNER	DOCUMENT KIND				
Head of Training Center	Agenda				
TITLE					
GIS-L3-ELK14_300&ELK3_420-Training Agenda					
OWNING ORGANIZATION	DOCUMENT ID	REV.	LANG.	PAGE	
CH-Zurich-2657-Field Service	2GHE004272	В	en	1/6	
Hitachi Energy © 2022 Hitachi Energy. All rights reserved.					



Course goal:

The course conveys profound knowledge on the assembly of GIS type ELK-14 / 300 and ELK-3 / 420

Main learning objectives:

- Understand the functions of all GIS components of ELK-14 / 300 and ELK-3 / 420
- Known about all relevant documents (drawings, instructions, protocols) to perform an installation
- Perform a complete GIS Bay ELK-14 / 300 assembly

Prerequisites:

- SF₆-Gas-handling course with certificate
- Heavy load course with certificate
- Good English skills (written and spoken)
- Ability to read wiring diagrams is required
- On-site experience on GIS Installation and/or Commissioning
- Attended the local required Health & Safety Training
- First aid course with certificate

Topics:

- Circuit-breaker and breaker operating mechanism
- Disconnector, earthing switch, fast acting earthing switch
- Statically components like connecting elements, busbars
- Lateral dismantling elements, compensators
- SF6-to-air bushing
- Surge arrester
- · Site assembly instructions

Assembly steps and procedures

- Overview and detailed drawings of assembly units, packing list and layouts
- · Positioning and alignment of CB
- Coupling and alignment of assembly units, busbars, compensators and exit bus
- Coupling and adjustment of transmission shafts of disconnector, earthing switch, fast acting earthing switch
- Corrosion protection and flange greasing
- Steel structures
- Earthing connections
- Protocols and Reports

This is a theoretical and practical training course.

Certification:

A confirmation will be issued after successful participation in this course, as part of the certification process.

Within a 12 months period, an on-site assessment must be carried out along with a final review to complete certification.

Duration:

20 days

Enrolments:

Send your request to

GIS-GCB_Training@hitachienergy.com

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE004272	В	en	2/6
0.000018 115 48111					

Day	Subject	Location
1	Welcome / Introduction to Hitachi Power Grids Switzerland Training Introduction / Presentation Safety Induction Certification Process ENERGY GIS-Product Portfolio GIS component ELK-14/300 and ELK-3/420 Circuit breaker SP14 and SP3 / HMB drive Disconnector/ earthing switch TK and BAC drive Fast acting earthing switch BAE Connecting elements and components Interfaces HK, HT, HB/HD	Classroom
2	GIS component ELK-14/300 and ELK-3/420 Continuation Continuation components Manual operation and locking device for disconnectors, earthing switches and fast acting earthing switches Gas monitoring system Density Monitor	Classroom
3	 GIS component ELK-14/300 and ELK-3/420 Continuation Continuation components Manual operation and locking device for disconnectors, earthing switches and fast acting earthing switches Gas monitoring system Density Monitor Factory tour to respective assembly line 	Classroom
4	Preparation and Unpacking of Assembly-Units Preparation of installation How to set up a construction site (site office and GIS building) First needed documents to start the installation Packing list GIS drawings GIS layouts	Classroom Training field
5	 Place and level the CB Measuring of the ground floor Marking of 'X' and 'Y' axes Setting and adjusting of CB-pole frame Alignment of the CB at determined 'X' and 'Y' axes 	Training field

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE004272	В	en	3/6
© 2022 Hitachi Energy, All rights recoved					

Day	Subject	Location
	Preparation and Unpacking of Assembly-Units	
6	 Continuation of place and level the CB Measuring of the ground floor Marking of 'X' and 'Y' axes Setting and adjusting of CB-pole frame Alignment of the CB at determined 'X' and 'Y' axes 	Training field
7	 Installation of Assembly-Units Basic steps for cleaning and installing the units Install of all three riser units Install of all three CT's (with regarding of CT polarity) Theoretical Part Installation Manual "Installation and Commissioning Procedure" 	Classroom Training field
8	Preparation and Unpacking of Assembly-Units Installation of Assembly-Units Basic steps for cleaning and installing the units Install of all three riser units Install of all three CT's (with regarding of CT polarity)	Classroom Training field
	Theoretical Part • Installation Manual "Installation and Commissioning Procedure"	
	Installation of Assembly-Units	
9	 Install of all three cable outgoing units, which contain a combined disconnector/earthing switch and fast acting earthing switch Align the units and assembling, incl. adjusting of the steel support 	Classroom Fraining field
	Theoretical Part	·
	Installation Manual "Instructions"	
	Preparation and Unpacking of Assembly-Units	
10	 Installation of Assembly-Units Install of BB units, incl. assembling and adjusting of the steel support 	Classroom Training field
	Theoretical Part	•
	Installation Manual "Instructions"	

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE004272	В	en	4/6
© 2022 Hitachi Engray All rights reserved					

Day	Subject	Location
11	Installation of Assembly-Units Install of BB units, incl. assembling and adjusting of the steel support Theoretical Part	Classroom Fraining field
	Installation Manual "Instructions"	<u>'</u>
	Preparation and Unpacking of Assembly-Units	
12	Installation of Assembly-Units Install of BB units, incl. assembling and adjusting of the steel support	Classroom Fraining field
	Theoretical Part	~ ⊢
	Installation Manual "Protocols"	
	Preparation and Unpacking of Assembly-Units	
	Installation of Assembly-Units	om ield
13	 Install of HK units, incl. assembling and adjusting of the steel support 	Classroom Training field
	Theoretical Part	D 5T
	 Measurements (Gas-quality, primary resistance) Schematic Diagram, cable list, cable glands, cable tray arrangement 	
	Installation of drive shafts / Hands on VQ	
14	 Install of DV-equipment according to instruction Disassembly and assembly of the separable connector VQ 	Nassroom aining field
	Theoretical Part	Cle
	Reporting (Field service report, Daily site report, Manpower list)	
	Disassembly and packing of Assembly-Units	
15	Disassembly of HK unitsDisassembly of BB units	Classroom Training field
	Theoretical Part	O E
	Red marks, VP, shares of supplies	

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE
Approved	Internal	2GHE004272	В	en	5/6
© 2022 Hitachi Engray All rights reserved					

Day	Subject	Location
	Disassembly and packing of Assembly-Units	
16	 Pack and upload of HK units Pack and upload of BB units Disassembly of BB units 	Classroom Fraining field
	Theoretical Part	F
	Earthing details	
	Disassembly and packing of Assembly-Units	
17	 Pack and upload of BB units Disassembly of BB units Disassembly of cable outgoing units 	Classroom Training field
	Theoretical Part	- F
	TA Update, new and updated Instructions	
	Disassembly and packing of Assembly-Units	
18	 Pack and upload of cable outgoing units Disassembly of CT's Disassembly of riser units 	Classroom Training field
	Theoretical Part	○
	Overview of handed out documents on the memory stick	
	Disassembly and packing of Assembly-Units	
19	 Pack and upload of CT's Pack and upload of riser units Pack and upload of the steel supports 	Training field
	Cleaning up the site	
	Exam	
20	Final Discussion	Classroom
	Farewell	O

STATUS	SECURITY LEVEL	DOCUMENT ID	REV.	LANG.	PAGE	
Approved	Internal	2GHE004272	В	en	6/6	
© 2022 Hitachi Energy, All rights reserved						